

SURVEYOR'S NAME J D M'Gregor 'A' 'B' CLASS Phone..... SHIRE..... 39
 PROPERTY OWNER Mengler LOCATION No.....
 DATE OF PLANNING & SURVEY 17-18:1:83 TOWN.....
 HAVE ALL LINES BEEN DRILLED..... Yes Y No..... AERIAL PHOTOS Yes.....No.....
 HAS CLIENT SIGNED BANK ORDER..... Yes Y No..... Infra red. Colour. Black & White
 TOTAL KILOMETRES SURVEYED..... SITE SUPERVISOR..... FARMER..... 'A' Class..... 'B' Class..... CONTRACTOR.....

LEGEND

BUSH		ROCK		DAMS		RIDGE (CONGLOMERATE, IRONSTONE, BREAKAWAY, SAND)		PIVOT POINT	
LEVEL BANKS	Blue	FUTURE	Red			FLOODWATER		TREES	
GRADE LINES	Blue					Trees		FENCES	
MACHINERY FLYOVER						LAKES		ROADS	
BORES & WELLS		Fresh		Salt		SALT SCALD OR WATERLOGGED COUNTRY			
SANDSEAMS						CREEKS			

'A' CLASS APPROVAL DATE

PROPERTY OWNER OR CLIENT'S SIGNATURE

COMMENTS

Mainly concerned with the fall necessary to conduct the water from the Boundary on the south side. At A & B on the south side I have made these legs level to ~~stead~~ steady the flow. I have introduced the lower grade line 2 into the line on the north Boundary at a point where the fall is a bit less (13cm in 30) so have put the step in at C, ~~stands~~ where there is a fairly steep fall. The line levels out at two points further east which should cope with the situation there. The clay is fairly uniform depth 6"-12" & its white gum. Gate country. A large proportion of the water does find its way down the firebreak at the moment without too drastic results. (so far)

